G. R. S. IX-5]

Previous references.

File No.

192

( )

Serial Nos.

Later references

1926-27 S 105 12

GENERAL AND REVENUE SECRETARIAT.

Serial Nos.

Part B for

SUBJECT.

WD 2231- GPB —20,000—11 6 20

G. R. S. III—1] 1920-21.

GENERAL AND REVENUE SECRETARIAT.

(Muzrai)

NOTES.

File No. 126-20

FILE HEADING.

Revised Estimate for the improvement of the Jumma Masjid at Mysore.

From

The Deputy Comm^r, Mysore Dt.

Ref. 4 No. 26 of 20-21. Dated 30.8.20. Received 31.8.20.

Diary No. 510	Enclos. 11 Spare Copies.	Serial No.

BRIEF ABSTRACT OF LETTER.

Submits for sanction a revised estimate amounting to Rs. 26400 for the above work in place of the original estimate for Rs. 18375 sanctioned in G.O. No. 49-52/Muz 467-18-2 d. 5.7.19 and state that in the present esti-

NOTES AND ORDERS.

mate some extra provision is made to construct an ornamental frontage & a new latrine which were not provided in the original estimate.

The previous file sanctioning the original estimate for Rs. 18375 in July 1919 is put up for perusal.

NOTES—First Sheet.

G. R. S. III-2]

General and Revenue Secretariat.

Mavj. File No. 126 of 1920.

Serial No.	
2	There is a fresh report by the Executive Engineer, Mysore Division, on the revised estimate. It is only about a little more than a year since an estimate for the large amount of Rs. 18375 was sanctioned for the improvements of the masjid in question. The D. C. however states that it is reported by the Supdg. Engineer that in the original estimate provision had not been made for the construction of an ornamental frontage and a new latrine and that the above extra items have been included in the revised estimate now submitted for sanction. It will be seen from the previous file that as a special case the cost a grant of Rs. 10000 was made from State funds and another grant of Rs. 6000 was ordered to be paid from the annual Muzrai State grant of Rs. 10000 in 2 equal instalments in 2 successive years and the balance of Rs. 2352 of the cost of the estimate was met from the savings which were then available at the credit of the insttn. It was stated in the G.O. sanctioning the estimate that the estimates were scrutinized by the

NOTE—Contn. sheet.

Serial No.

the Chief Engineer and that they provided for all the needs of the institution. The Supdtg Engineer's letter referred to in the D. G.'s communication is not among the enclosures received with the D. G.'s letter. It is learnt that there was only a sum of Rs. 281-8-10 at the credit of the instn on 30th June 1920.

Submitted for orders

MAV.

4.9.20. To the Asstt Engr. for his comments for favour of sending remarks.

RG

3.9.20 The estimate is in order and may be sanctioned.

Asst Engr

Mvg Engr)

4. Now arises up the question of the source from which this large sum of Rs 26,400 should be met. The original estimate of Rs 18375 was ordered to be met from the following sources:-

1) 10000 Rs Spl grant for Spl reserve in the 19-20 budget under 13 Misc

2) 2352 from Savings of the inst.

3) 6023 from State Grants of 19-20 and 20-21.

Rs 18375

G. R. S. III-2]

General and Revenue Secretariat.

Mwz. File No. 126 of 1920.

Serial No.

26400
18325
8025

5. The revised Estimate is the new Target for Rs 26,400 which is 8025 Rs more than the previous Estimate, ~~the special grant of 20,000 Rs~~ ~~sanctioned~~ Orders are solicited as to the Sources from which the Charge should be met

B/
29-9-20

6. ~~Why~~ How have the work Should be Carried out-

7. ~~If~~ ~~it~~ ~~only~~ ~~Noble~~ ~~Minister~~ ~~is~~ ~~to~~ ~~diminish~~ the expenditure over 2 or 3 years, the additional required may be provided out of the State grant or the General Municipal Fund ~~in~~ by instalments, so as ~~to~~ ~~keep~~ ~~up~~ work actually Carried out each year.

Attn
30/9/'20

(Secy)

8. The Municipality Cannot well afford to spare the additional sum of Rs 80·25 required

Second Member) W J 8/10/20

9. It is unfortunate that

2238-198
10-10-20.

NOTE—Contn. sheet.

R. S. III-2.

General and Revenue Secretariat.

Muz File No 126 of 1920

Serial No.

been omissions — nothing unusual — Lawyer — & a revision of the Estimate enhancing cost by nearly 35 p.c. But the work has got to be carried out & that is certain. & the suggestion the additional amount being found by Expenditure being spread over at least two of the succeeding years. Has to the Irrig. Dept. & the Executive? If so. & it is to be done.

Bell.
12.10.20

13/10/20

3.10.

10. Forwarded with compliments to the Secy. to Govt. Financial Dept. for favour of opinion.

Sd/- A. [illegible]
for Secy. to Govt.
Muz Dept.

SPECIAL SECRET
K991-20
4

Memorandum
13.10.20

11. The position is one of deficit and no additional Grant to the Muzaffarpur Dept is therefore possible.

Sd/- [illegible]
15/10/20

Muz Secrett).

12. There is no question of adding to the Muz. grant but

NOTE—Contn. sheet.

R. S. III-2,

General and Revenue Secretariat. | MWR File No. 126 of 1920

Serial No.

The proposal is simply to allot the funds required to instalments out of the State grant originally provided for in the Revised Budget for purposes of relief.

Asst
16/10/20

Fml Sects)

13. Submitted with reference to the Fl Secys note dy 15-10-20.

Hm 27-10-20) 14. If it is possible to continue the Grant of Rs 10,000, there is no financial objection to a share of it being assigned for this purpose.

15. Considering the general financial position it is difficult to say now if the said Grant can be repeated next year -

1.11.20

Mungyeeli)

18
2/4

Asst
3.11.20

To Secy)

Gerald Kunkel)

16. If the State Grant ceases then this Expenditure must also cease to exist.

2606.2/4
6.11.20.

NOTE—Contn. sheet.

G. R. S. III-21

General and Revenue Secretariat.

Muz File No. 126 of 1920.

Serial No.

So long as that is the source fr ch. Bnd. The work has got the deve and pechip are shing in the matter. The file may nav be submitted to the Dewan

Revd. 8.11.20

Dewan 8/11/20

17. I agree with the remarks

12.11.20

18.

13/11/20

19. Submd with draft order sanctioning the revised estimate.

MR.

13 11. 20. Mem No 49-52/M: 467-18-2 dy 5.7.19 am. Estimate of Rs 18,375 for the work was sanctd. the sources of meeting the cost being as follows:-

Rs 10,000 from the Special reserve made in the budget under 13 Misc.

Rs 2,352 Savings at the credit of the Misc.

Rs 6023 State grants in 2 instal ts for 1919-20 and 1920-21

DEWAN'S OFFICE.
Recd. on NOV 10 1920
3590

NOTE—Contn. sheet.

G. R. S. III-21

General and Revenue Secretariat.

Mazg. File No. 126 of 1920

Serial No.

21. Now an add. sum of Rs 8,025 has been sanctioned & the work
Nothing has been ascertained from
A. the Comptroller's Office that the sums of Rs 10,000 and Rs 6023 resp. to above have already been credited to the Institution funds.

22. Orders are solicited as to whether the add. amt of Rs 8,025 may be sanctioned from the State grant allotment of this year 1920-21 and of next year 1921-22 in two equal instalments?

23. Kind reference is invited in this Connn to the remarks of the Fl. Sec dd 11.11.20 expressing a doubt as to the possibility of repeating the State grant allotment next year. (Page 6 supra).

24. Specific orders are solicited in the matter.

Rd 15/11/20 It must clear what work has been done in pursuance of the original Estimate of Rs 18372; if no work has yet been done, there is no doubt in sanctioning allotment

NOTE—Contn. sheet.

Serial No.

further funds from the current year's grant to the prejudice of the more pressing needs of other Dists: where payments may be actually due --

26. In these circs:, it will be useful if orders be issued.

(1) Sanctg the revised Estimate for Rs. 26400.

and

(2) informing the Dy. that, as the work is carried out, payments may be made from the additional allotments already sanctd on the original Estimate.

and (3) that and that the bills for further works of Edn. may be submitd direct for Orders regarding formal provision of funds - and payment --

27. On receipt of the bills, which will be in the after the works to the extent of Rs 18-375 have been carried out - Asst

NOTE—Contn. sheet.

S. III-2]

General and Revenue Secretariat. | Mwz. File No. 126 of 1920.

Serial No.

the Question of finding provision the S.

– for the addl. works. within the limit of the revised Estimate –. may be Con- -sidered in the light of the Minutes recorded and Orders passed for payment from such funds – State grant or other funds – as may be available at the time –.

Asst
22/11/20

Secy)

28. Draft. Put up when the time comes to sanction the Amount out of the State Grant 1920-21

Asst 25/11

29. Submitted with draft as per orders.

MAV.

1.12.20. 31. If the Estimate for addl. sanctioned, the Amount of Rs 8025 required should be sanctioned when the

30. D.O. Blanks

Asst 18/12/20

NOTE—Contn. sheet.

G. R. S. III-2

General and Revenue Secretariat.

Mwz. File No. 126 of 1928.

Serial No.

Cannot be paid for the works -

32. Refce is requested to my D.O refce to Dr Comptr & his reply - (Fl-N + (4))

33. The Dr Comptr states that the full amount of Rs 18375- sanctd in Jan 19 has been placed at disposal of P.W.D

34. It will take some time for the P.W.D to carry out the works and the further sum of Rs 8025 req^d. may be allotted from the State grant or other source when time comes for payment after works & the amount of Rs 18375 have been fully carried out & paid for -. Draft P. for sgd -

Allotted
[illegible]

NOTE—Contn. sheet.

35. Wdly)

G. R. S. III-2]

General and Revenue Secretariat.

Irrig. File No. 126 of 1920.

Serial No.	
36.	Put up a fair draft U/ 21/12/20 MMC 21-12-
37.	Typed draft subm. MR. 22.12.20.
	All: 23/12/20
	To Secy.) A draft is put up Second Member 23/12/20
3592-184 27.12.20.	Draft approved by Dewan. 30.12.20. Mine U/ 31/12/20
2.	To, Ch. Engineer, P.C. Irrigation, Coimbatore Irrig. Supdt. Cauvery, to his Secret No. 2402-00 dt. 12.1.21. Sanction Re-Revised estimate for Rs 26 400/- for improvements to the Gun—a Irrigation scheme

NOTE—Contn. sheet.

G.R.S. III—3]

Routine Notes.

[To be used only for notes, requisitions, etc., not intended for permanent record.]

Dear Sir

Please see E.E.
No-49-520/. 5/Jan/19.
Sanctg. Rs 18375- for the
Repair of the Jamma
Masjid @ Ngome-
I send the file herewith
Effect -

The Dy has submitted a
revised Estimate for
Rs 26400/- & he does
not state how much
~~expenditure~~ has been
spent already on
the originally sanctd
Estimate -

= In the E.E's circular
that the Masjid's
Architect

N.B – Should routine notes be written on small slips the notes must be copied, or slips pasted on this form

Routine Notes.

[To be used only for notes, requisitions, etc., not intended for permanent record.]

Irrigation works to the amount
of June (Mehmandy) the
Waqf had Rs 1,12,281-8-10.
at Credit on 30 June 1920

I therefore request that
Sanction be let me know:—
(1) Whether Any expenditure
was incurred on this work
in 1919-20 & if so, how much
& how was it met?.

(2) Has Any portion of the State
funds Granted been credited to the
Waqf funds for this work if so
how much
(3) what is the balance now
at Credit of the Waqf?

N.B.—Should routine notes be written on small slips the notes must be copied, or slips pasted on this form.

I request the favor of a very early reply

Yours
A. [illegible]

Bangalore
20th December 1920

Dear Sir,

In reply to the three points raised in your D.O. dated the 18th Dec. 20 I append below the nature of adjustment of the sum of Rs 18.375/- sanctioned, for the improvement of the building of Jamma Masjid at Mysore, in G.O. No. 49-52 Mus 467-18-2 dy 5.7-19.

Rs 10.000/- from Special grant. This sum was directly transferred from 13 "Construction and repairs" to P.W. department in the accounts for October 1919.

235-2 From the savings at the credit of the Justice.
3012. From the State grant of 19-20. These two items were credited to P.W.D. in Oct. 1919.
3011 - From the State grant of 1920-21. This was also transferred to P.W.D. in July 20

18.375-. Thus the total sum of Rs 18.375/- was placed at the disposal of the P.W.D as directed in the G.O. referred to.

2. The answers to the three points raised in your D.O. is as follows:-

(1). The account having been placed at the disposal of the P.W.D, that Department carries out the work and a sum of Rs 3189-5-0 has been expended by them. kept.

2. All amounts except Rs 10.000/- mentioned above were credited to the Imprest Funds and then transferred to P.W.D.

3) The balance at the credit of the institution on 30th June 20, is Rs 281-8-10

Yours sincerely,
A. Swaminathan Iyer
20.12.20

20

A. Swaminathan Iyer Esqr.
Assistant Secretary,
Emigration department.
Bangalore.

SHAR No. 5.10

20-21

Mewz

126-20

1

1920-21

From The Deputy Commr
Mysore District

To The Secretary to Govt
Muzrai Department
Bangalore

Dated

Despatched 28th. aug 1920

Received

General No. Rep 26/20-21
No.

Enclosure No. 11

Submits for sanction a revised Estimate for Rs 26,400/ for improving the Jamma Masjid at Mysore

---

[illegible] Deputy Commissioner,

[illegible] 28th [illegible].

[illegible]

[illegible]

[illegible]

[illegible]

[illegible]

[illegible]

[illegible].

Sir,

As desired by the Superintending Engineer Western Circle in his letter No.24 dated 8th July 1920, I have the honor to forward herewith for favor of obtaining the sanction of Government a modified estimate for Rs.26,400/- duly countersigned, together with plans and a report for improving the Jamma Masjid at Mysore received from the above Officer.

2. The Superintending Engineer states that in the present estimate, some extra provision is made to construct ~~and~~ an ornamental frontage/a new latrine as shown in the enclosed tracing plan which were not provided in the original estimates and that the enclosed report explains the details of proposals.

3. The original sanctioned estimate and plans received with the above are also submitted herewith for reference.

I have the honor to be,

Sir,

Your most obedient servant,

For Deputy Commissioner,

Proceedings of the Government of H. H. the Maharaja of Mysore.

Read:-

Government Order No. 19452/Mun.467-18-2 dated 5th July 1919, sanctioning an estimate for Rs.18,375/- for effecting certain improve-ments to the Jumma Masjid at Mysore.

Paper under disposal. (2) Letter No.C.26 of 20-21 dated 30th August 1920, from the Deputy Commissioner, Mysore District, submitting for sanction a revised estimate for Rs.26,400/- for the above work.

2402—05 Exec Tender

Order No. Immai 126-20-2

Dated Bangalore, the ~~December 1920.~~ 12.1.21

The revised estimate which has been prepared by the Executive Engineer, Mysore Division, provides for the construction of an ornamental frontage and a new latrine for which no provision had been made in the original estimate.

2. The revised estimate for Rs.26,400/ is sanctioned.

3. As a large sum of Rs.18,375/- has been already made available for the work in the Government order of 5th July 1919, read above, the Deputy Commissioner may apply to Government for further orders regarding the additional sum of Rs.8,025/- required, after the allotment of Rs.18,375/- has been fully expended in payment for works actually carried out.

carried out.

11/23/12/20

Secretary to Government,

Muzrai Department.

To

The Chief Engineer of Mysore.

The Deputy Commissioner, Mysore District, with the sanctioned estimate, plans and other enclosures.

The Comptroller to Government, with a copy of the abstract estimate.

The Muzrai Superintendent in Mysore.

~~Memo No.~~ 2406 ~~dated Bangalore,~~ 12/21 ~~Dec. 1920~~

Copy to Financial Secretariat.

HRR.

51.	Painting with Silicate.	Sqr.	6-0-0	6.36	38/-
52.	Teak-wood work wrought and put up.	Cft.	6-0-0	125.06	750/-
53.	Teak-wood old.	Cft.	1-0-0	72.66	73/-
54.	-Do- planks ½" thick.	Sqr.	0-10-0	~~1085~~ 1052	~~105~~/-92
55.	Roofing with 1st class Mangalore tiles with 2" X 1" teak reapers complete.	Sqr.	32-0-0	31.50	1,008/-
56.	Riding tiles Mangalore and painted with cement.	Rft.	0-10-0	168	105/-
57.	Ventilating tiles.	Each.	2-8-0	25	62/-
58.	Putting chunam borders 6" X 4".	Rft.	0-3-0	44	8/-
59.	Burnt brick in coping ½" with plastering.	Rft.	0-8-0	34	17/-
60.	Constructing cement concrete plinth drain allround.		1-0-0	159	159/-
61.	Teak-wood ornamental eave board 1" X 9".	Rft.	0-12-0	329	247/-
62.	Preparing and fixing teakwood finials turned.		4-0-0	4	16/-
63.	-Do- eave conduit.		2-8-0	6	15/-

CONSTRUCTING A DOUBLE LATRINE.

64.	Earth-work excavation.		0-11-0	1.74	1/-
65.	Burnt brick in chunam average.	Cft.	0-4-4½	645	176/-
66.	Burnt stone slabs 6" thick -- roughly dressed.	Sft.	0-10-0	186	116/-
67.	Plastering with chunam.	Sqr.	3-8-0	1053	37/-
68.	Painting with cement mortar.		3-0-0	1.76	6/-
69.	Burnt brick in chunam coping including plastering allround.	Rft.	0-8-0	72	36/-
70.	Constructing cement concrete plinth drain.		1-0-0	25	25/-
71.	Clearing site and levelling and other works and forming road.	L.S.			200/-
72.	Unforeseen works.	L.S.			200/-
73.	Improving the floor bed in front and constructing dwarf-wall of brick-in-chunam for flower beds.	L.S.			150/-
74.	Filling the bed of pond with surki concrete and painting the joints with cement.	L.S.			160/-
75.	Examining the water-tap with necessary platform, etc.	L.S.			50/-
76.	Contingencies @ 5%...	L.S.			1,249/-

GRAND TOTAL.Rs.26,400/-

"C O P Y."

for Secretary to Government,

Muzrai Department.

HRR-3./10-1-21.

estimate of the probable cost of improving the Jumma ---

at Mysore.

No	Items of work.	per.	Rate.	Quantity.	Cost.
	CONSTRUCTING FRONT WALL WITH TOWER.				
1.	Dismantling the existing front and side compound walls. (a) Northern side of Masjid and carting.	L.S.			250/-
2.	Earth ~~Earth~~ work excavation hard soil.	Units.	0-15-0	90.49	85/-
3.	Concrete in chunam.	Cft.	0-3-6	1853	405/-
4.	Burnt brick in chunam foundation and basement.	Cft.	0-4-3	7504	1,993/-
5.	-Do- octagonal 49½' high.	Cft.	0-5-6	6205	2,133/-
6.	-Do. superstructure.	Cft.	0-4-6	6578	1,850/-
7.	Plastering with chunam.	Sqr.	3-8-0	133.21	466/-
8.	Cornice work 1¼ X 1¼.	Rft.	1-4-0	185	231/-
9.	Parapet ornamental 2½' high as per plan.	Rft.	1-8-0	184	276/-
10.	-Do- 8' high -Do-	Rft.	5-0-0	41	205/-
11.	Moulding work above basement in superstructure.	Rft.	0-4-0	262	65/-
12.	Mortar ornamentation with top panels and foliated arch including carving of bays. (as per plan).	No.	10-0-0	17	170/-
13.	-Do- in centre (as per plan).	No.	12-0-0	2	24/-
14.	Constructing pillasters and base cap 13 ' as per plan.	No.	25-0-0	19	475/-
15.	Pillasters at sides of gateways including top and bottom with expanded metal to Dome work 39' as per plan.		60-0-0	4	240/-
16.	Burnt stone brackets for railing in tower as per plan.	Sft.	5-0-0	64	320/-
17.	Railing with expanded metal to tower as per plan.	Sft.	1-0-0	324	324/-
18.	Burnt stone slabs 6" nicely dressed.	Sft.	0-10-0	216	135/-
19.	Constructing expanded metal dome with posts, etc., as per plan.	No.	500-0-0	4	2,000/-
20.	Repairing and fixing teakwood door ornamental as per plan. Design to be furnished during execution.	Sft.	4-0-0	65	260/-
21.	Burnt brick in chunam coping and plastering complete with fixing glass pieces at it.	Rft.	0-8-0	246	123/-
	MASJID PROPER INCLUDING COURT YARD.				
22.	Dismantling ~~to~~ existing tower northern wall and parapets, etc., and carting debries - outside and levelling.	L.S.			100/-
23.	Repairs to existing cracked walls and removing the -- plants grown over the walls.	L.S.			50/-
24.	Dismantling the existing terrace and carting debries outside.	100 Cft.	0-0-9	21.45	101/-
25.	Removing the existing planks as per dismantling.	Sqr.	1-8-0	21.45	32/-

Continued.

26. Teak-wood wrought and put up 1¼ frame centre to centre.	Cft.	6-0-0	208.76	1,254/-
27. Roofing with pucka terrace 9" thick brick on edge ---. flat tiles, with 3 surki concrete.3 courses of flat tiles and plastered over.	Sqr.	32-0-0	21.45	687/-
~~28.~~ with chunam etc., complete as per dismantling.				
28. Providing water spouts wherever necessary.	L.S.			50/-
29. Wood oiling.	Sqr.	3-0-0	23.99	72/-
30. Constructing ornamental cornice 9½ X 9" exterior.	Rft.	0-12-0	182	136/-
31. -Do-Do- parapets over the terrace with pannels, and plaster and 9" thick and 3' high with plastering finials.	Rft.	1-8-0	176/	264/-
32. Constructing ornamental cornice 6" X 6" inside.	Rft.	0-8-0	130	65/-
33. White washing walls inside two coats.	Sqr.	0-6-0	19.58	7/-
34. Flooring with Mangalore flooring tiles over 3" concrete and painted over with cement.	Sqr.	35-0-0	20.00	700/-
35. Flooring with Cuddapa slabs over 3" concrete and painted over with cement.	Sqr.	35-0-0	37.98	1,330/-
36. Constructing cement concrete plinth drain allround the court yard.	Rft.	1-0-0	180	180/-
37. Cutting and removing the existing trees, shrubs, bushes, etc., with roots.	L.S.			25/-

CONSTRUCTING MUSAFIRKHANA NEW.

38. Removing and pot tiles roof dismantling the mud walls carting outside and levelling the ground.	L.S.			150/-
39. Earth-work ~~earth~~ excavating and filling basement.		0-15-0	38.20	36/-
40. Concrete in chunam.	Cft.	0-3-6	469	102/-
41. Burnt brick in chunam foundation and basement.	Cft.	0-4-3	4320	1,148/-
42. -Do- superstructure.	Cft.	0-4-6	4076	1,146/-
43. Burnt stone slabs 6" thick nicely dressed.	Sft.	0-10-0	326	204/-
44. Plastering with chunam mortar.	Sqr.	3-8-0	71.80	251/-
45. White-washing two coats.	Sqr.	0-6-0	71.33	27/-
46. Teak-wood doors battened with iron bars new ¾" in diameter and 1" shutters and -- hinges, rings, etc., complete.	Sft.	2-4-0	36	81/-
47. Teak-wood gate shutters and teak reapers hinges and iron		2-0-0	30	60/-
48. Cut stone pillars 9" X 9" square and 8' long and stone base capital.		14-0-0 ~~0-14-0~~	10	140/-
49. Flooring with Kaddapa slabs on over 3" concrete and painted over with cement.	Sqr.	35-0-0	23.62	827/-
50. Flooring with Mangalore Tiles over 3" concrete bed and painted with cement.	Sqr.	35-0-0	5.04	176/-

Continued